

TECHFLOW INSTRUMENTATION LTD - VENDOR INVOICE

Invoice Number: TF-2026-8891

Invoice Date: 2026-08-28

Customer: Mangalore Refinery and Petrochemicals Ltd (MRPL)

Purchase Order: PO-MRPL-42009

Item 1: High-Precision Pressure Transmitters (PT-101 series) x 4 units - \$8,400.00

Item 2: Ultrasonic Flow Sensor Assemblies (FT-205 series) x 2 units - \$6,450.00

Total Amount Due: \$14,850.00

Remittance: Wire Transfer to Standard Chartered Bank, A/C #992837102

TERMS OF SUPPLY AND COMMERCIAL CONDITIONS

Delivery Terms: Incoterms 2020 DDP Mangalore Refinery Gate 3

Payment Terms: Net 30 days from date of receipt of material

Penalty Clause: 0.5% per week of delay subject to max 5%

Taxes and Duties: GST 18% inclusive as per statutory regulations

Packing: Export-grade seaworthy wooden cases with moisture barrier

Insurance: Comprehensive transit risk coverage by supplier until handover

EQUIPMENT TECHNICAL DATASHEET - PT-101 / FT-205

Operating Pressure Range: 0 - 250 PSI (Calibrated 80 - 150 PSI)

Operating Flow Range: 100 - 600 GPM (Calibrated 350 - 500 GPM)

Wetted Material: 316L Stainless Steel with Hastelloy diaphragm

Enclosure Protection: IP67 / NEMA 4X weather-proof housing

Output Signal: 4-20 mA HART dual-channel telemetry

Hazardous Area Certification: ATEX Zone 1, Ex d IIC T4 Gb certified

FACTORY ACCEPTANCE AND CALIBRATION RECORD

Calibration Reference Standard: Fluke 754 Documenting Process Calibrator

Zero Calibration Drift: < 0.02% of full span over 24h

Span Calibration Deviation: < 0.04% at 150 PSI test bench

Hydrostatic Test Pressure: 375 PSI held for 30 minutes without drop

Helium Leak Rate: < 1.0×10^{-8} mbar.l/s at ambient

Testing Engineer: S. Bannerjee (Quality Assurance Dept)

MATERIAL TEST CERTIFICATE EN 10204 3.1

Heat Number: HT-99824-A

Chemical Composition: C: 0.022%, Cr: 17.2%, Ni: 12.1%, Mo: 2.45%

Tensile Strength: 585 MPa | Yield Strength: 245 MPa

Elongation: 45% | Hardness: 165 HBW maximum

Corrosion Resistance Test: ASTM A262 Practice E passed without fissuring

Non-Destructive Testing: 100% Ultrasonic & Dye Penetrant inspected

WARRANTY AND LIABILITY SCHEDULE

Standard Warranty Period: 24 months from commissioning or 36 months from dispatch

Defect Rectification: Replacement within 14 working days of notification

Exclusions: Normal wear and tear, operational overpressure beyond 150% rating

Limitation of Liability: Capped at 100% of order value

Governing Law: Republic of India jurisdiction, Mumbai arbitral seat

ANNEXURE D: SPECIAL OPERATIONAL CONDITIONS & REGULATORY NOTES

Section D.1: Regulatory compliance verification requirement

Section D.2: Mandatory quarterly recalibration by certified personnel

Section D.3: Emergency shutdown isolation protocols

Section D.4: Environmental safety and disposal regulations

All operational protocols must conform to ASME Section VIII Div 1.

AUTHORIZATION AND SIGN-OFF SHEET

Lead Commissioning Engineer: _____ Date: _____

Plant Maintenance Superintendent: _____ Date: _____

Quality Assurance Manager: _____ Date: _____

Finance & Accounts Approval: _____ Date: _____

Status: PENDING AUDIT VERIFICATION